



PARTIAL FRAMING PLAN - TOS EL: 106-1 (U.N.O) N

(REF: 27-9-D-70016)

- NOTE:
- 1) \* INDICATES CONNECTION BETWEEN BOTTOM FLANGE OF BEAM AND HORIZONTAL BRACES WITH SHIMS
  - 2) ALL FIELD BOLTS ARE 7/8" DIA A193, GRADE B8, CLASS 2, TYPE 304 (U.N.O)
  - 3) ALL INDICATES 3/4" DIA BOLTS A193, GRADE B8, CLASS 1, TYPE 304
  - 4) # INDICATES BEAMS WILL BE INSTALLED AFTER EQUIPMENT IS SET AS DIRECTED BY HONEYWELL

- NOTE(S):
- 1) CONTRACTOR TO FIELD VERIFY ALL DIMENSIONS AND ELEVATIONS PRIOR TO FABRICATION AND INSTALLATION.
  - 2) CONTRACTOR AND/OR E.O.R. TO PROVIDE ALL HANDRAIL POST LOCATIONS.
  - 3) E.O.R. TO VERIFY ALL CONNECTIONS.
  - 4) ALL VERIFIES WILL BE ASSUMED CORRECT AS SHOWN UNLESS NOTED OTHERWISE BY APPROVER.

SEQUENCE-04

ALL ERRORS IN FABRICATION MUST BE REPORTED TO THE FABRICATOR WITHIN 24 HOURS FOR DECISION AS TO THE BEST METHOD OF CORRECTION. BACK CHARGES WILL NOT BE ACCEPTED UNLESS OUR CONSENT IS GIVEN IN ADVANCE. IN WRITING.

REVISIONS			JOB	
REV	DATE	BY	DESCRIPTION	LOCATION
A	09-28-15	VPM	ISSUED FOR APPROVAL	CUSTOMER
				ARCH/ENGR
				TITLE
				DRAWN VPM DATE 09-28-15 CHK'D VPG DATE 09-28-15
				JOB NO: 15-32
				DWG NO: E401